

DESCRIPTION


PMI MODEL NO. PFA-DC18-10dB-10W-NFM IS A FIXED ATTENUATOR THAT OPERATES OVER THE FREQUENCY RANGE OF DC TO 18.0 GHz.

REVISIONS				
ZONE	REV.	DESCRIPTION	DATE	APPROVED
	-	PRELIMINARY	8/29/2023	

MECHANICAL OUTLINE

SPECIFICATIONS

- FREQUENCY RANGE: ----- DC TO 18.0 GHz
- IMPEDANCE ----- 50 OHMs
- VSWR (RETURN LOSS): ----- 1.4 MAX (15.6 dB MIN)
- INPUT POWER: ----- 10 Watts
- DEVIATION (+/-dB): -----
 - DC TO 4 GHz - 0.5
 - 4 TO 8 GHz - 0.6
 - 8 TO 12.4 GHz - 0.7
 - 12.4 TO 18 GHz - 1.0
- RF CONNECTORS IN/OUT: ----- N TYPE FEMALE / MALE
- ATTENUATION VALUE: ----- 10 dB NOMINAL
- BODY: ----- STAINLESS STEEL PASSIVATED



ENVIRONMENTAL RATINGS

- HUMIDITY: ----- MIL-STD-202, METHOD 106
- SHOCK: ----- MIL-STD-202, METHOD 213B COND. G
- VIBRATION: ----- MIL-STD-202, METHOD 204D COND. B
- ALTITUDE: ----- MIL-STD-202, METHOD 105C COND. B
- TEMPERATURE CYCLE: ----- MIL-STD-202, METHOD 107D COND. B

ABSOLUTE MAXIMUM ENVIRONMENTAL RATINGS

- TEMPERATURE: ----- -55 °C TO +125 °C

PERMANENT DAMAGE MAY OCCUR IF ANY OF THESE LIMITS ARE EXCEEDED.

ALL DIMENSIONS
ARE IN INCHES [mm]
TOLERANCES:
X.XX ±0.020
X.XXX ±0.010

PMI CONFIDENTIAL AND PROPRIETARY

NOTE: SPECIFICATIONS WILL VARY OVER OPERATING TEMPERATURE
NOTE: THE ABOVE SPECIFICATIONS ARE SUBJECT TO CHANGE OR REVISION

PLANAR MONOLITHICS INDUSTRIES, INC.
7311-F GROVE ROAD
FREDERICK, MARYLAND 21704 USA
TEL: (301)-662-5019, FAX: (301)-662-1731
WEB: www.pmi-rf.com, EMAIL: sales@pmi-rf.com
ISO 9001 CERTIFIED



		TITLE PRODUCT FEATURE PFA-DC18-10dB-10W-NFM				
APPROVALS	DATE					
DRAWN <i>AF</i>	8/23/23					
REDRAWN		SIZE A	FSCM NO. 05XQ0	DWG NO. PRELIMINARY	REV. -	
ISSUED		SCALE N:S			SHEET 1	OF 1